

MAKES OF KITCHEN EQUIPMENTS

- AIR CURTAIN/insect couter- VTS/AVRO
- WATER COOLER- VOLTAS/BLUE STAR/
- REFERIGERATOR- ELECTROLUX/FOSTER
- COAL TANDOOR—MUNNI LAL
- PLUMBING FAUCETS- JAQUAR/PARKO/
- BURNERS – HPC, VALAVES- SAKHA
- FLEXIBLE GAS PIPES –SURAKSHA GI BRADED/ISI MARKED.
- LIGHT FITTINGS- PHILIPS/BAJAJ/C.G. (CFL TYPE)
- FASTNERS- HILTI
- WHEELS- JAINSON
- LOCKS/PADLOCK- GODREJ.

GENERAL SPECS

- KITCHEN EQUIPMENT LAYOUT IN AUTO CAD FORMAT ALONG WITH THE ALL SERVICES SHALL BE PART OF SUBMISSION OF OFFER COMPLETE IN ALL RESPECT.
- ALL KITCHEN EQUIPMENTS SHALL BE OF SS 304 INCLUDING THE FRAME WORK. SQUARE PIPES SECTION(40x40) REQUIRED FOR BASE AND LEGS OF ALL GAS RANGES, HOT PLATES SINKS, TABLES , RACKS ETC.
- ALL EQUIPEMENTS SHALL HOLD THE WARRANTY OF ONE YEAR FOR ANY DEFECTS. S.S QUALITY LAB TESSTING MAY BE DONE , AT THE COST OF VENDOR.
- COLD ROOM- S S PANEL WITH VIEW WINDOW. CHEQUERED PLATES ON DOORS. (BOTH SIDES) CORNER ANGLES AT ALL JUNCTIONS ON PANLES. 100 MM THICK PUFF PANEL. TEMP. DISPLAY UNITS -2 NOS EACH FOR EACH COLD ROOM. (ONE DISPLAY WILL BE CENTRALISED, WITH BUZZER FOR ALL THREE COLD ROOMS) . DUAL BUZZER IN EACH COLD ROOM. CABLEING AND PIPING SHALL BE ON CABLE TRAY. OUTDOOR RACKS WITH TOP COVERING FOR OUTDOOR UNITS(ONE RACK EACH FOR 2 OUTDOOR-3RACKS). INSULATION SHALL BE COVERED WITH CHEMICAL COATING AND FABRIC. STRIP CURTAINS FOR EACH UNIT.
- OUTDOOR UNIT SHALL BE MOUNTED ON RACKS (ONE RACK SHALL ACCOMODATE 2 UNITS) , MADE OF WELDED SS WIRE MESH (AS PER APPROVAL) WITH LOCK ARRANGEMENT. COVERED FROM TOP. IP 65

MCB, ELCB BOX WITH SUITABLE OUTGOING SHALL BE PART OF SCOPE OF SUPPLY FOR THE ALL THE UNITS.

- **SCOPE SHALL INCLUDE THE LOADING /UNLOADING /SHIFTING AND INSTALLATION AND COMMISSIONING AT SITE.(ALL ACCESSORIES SHALL BE INCLUDED IN THE INSTALLATION AND COMMISSIONING LIKE FASTNERS, PLUG TOP, DRAIN PIPES-G.I. , FAUCETS, FLEXIBLE GAS PIPES, FLEXIBLE WIRE UPTO 1.5 MTR OF SUITABLE RATING FOR CONNECTING/ENERGISING THE EQUIPMENTS, ANGLE VALVES , SINK MIXTURES, GAS REGULATOR ETC.**
- **GA DRAWING SHALL BE SUBMITTED FOR THE APPROVAL WITHIN 7 DAYS OF THE AWARD OF CONTRACT.**
- **SITE SURVEY IF REQUIRED SHALL BE IN PART OF SUPPLIER.**
- **IT IS UNDERSTOOD THAT VENDOR HAS DONE THE SITE SURVEY BEFORE THE SUPPLY OF EQUIPMENTS. NO MODIFICATION IN THE SITE WILL BE ENTERTAINED WHATSOEVER DURING THE INSTALLATION AND COMMISSIONING STAGE.**
- **PAYMENT TERMS- 10% ADVANCE**
 - 30% AGAINST THE APPROVAL OF GA DRAWING**
 - 45% AGAINST THE DELIVERY OF EQUIPMENTS AT SITE**
 - 10% AGAINST THE FINAL INSTALLATION /COMMISSIONING /HANDOVER OF EQUIPMENTS AT SITE.**
 - 5% B.G. FOR YEAR AGAINST DEFECT LIABILITY PERIOD.**
- **DELIVERY PERIOD 30 DAYS FROM THE DATE OF APPROVAL OF GA DRAWINGS**
- **PENALTY CLAUSE- 5% OF THE ORDER VALUE FOR DELAY AFTER 30 DAYS PER DAY.**
- **ALL THE EQUIPMENTS AT SITE SHALL BE INSTALLED AND COMMISSIONED WITHIN 7 DAYS FOR THE DELIVERY AT SITE OR ELSE PENALTY WILL BE IMPOSED @ 1% OF 10% AGAINST THE INSTALLATION AND COMMISSIONING.**
-

